

Case Study

Restoration - Kings Sterndale

Location: Kings Sterndale

Project: Sympathetic Restoration – Phase 1

Project Length: 20 Weeks

Information:

Building Projects (UK) Ltd were contracted to carry out restoration and refurbishment at Christ Church Kings Sterndale.

The church was in need of urgent structural repairs. Bulging walls and buttresses were numbered and photographed. Stone work was carefully dismantled and re-built using hydraulic lime and limestone dust mix.

Works Included:

- Structural ties
- Re-building the nave west wall and adjoining buttress.
- Structural repairs to the channel north wall.
- General re-pointing
- Stonework repairs
- Roof repairs

Phase 1 was completed ahead of time, with great satisfaction from the client.

Building Projects are soon to start the second phase which involves more restoration works.

